BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: **Reserve fund for Emergency works in Dasarahalli Ward No.15** (Construction and Improvements of RCC roads and Drains at Model Colony Ayyappa Choultry back side road R/s in ward no.15, Dasarahalli)

Sl. No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods Complete as per specifications.	Cum	81.68	81.00	Rupees Eighty One Only
2	Plain cement concrete 1:3:6 mix with crushed stone aggregates 40m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14days Complete as per specifications.	Cum	10.46	3654.72	Rupees Three Thousand Six Hundred Fifty Four and Seventy Two Paise Only
3	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating curing and necessary steel or ply wood or plank centering and form work etc., including smooth finish in CM 1:3,with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed cement concrete for beams, columns, staircase and roof with Complete as per specifications.	Cum	27.20	5535.32	Rupees Five Thousand Five Hundred Thirty Five and Thirty Two Paise Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specifications.	q	12.00	7187.86	Rupees Seven Thousand One Hundred Eighty Seven and Eighty Six Paise Only
5	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour Complete as per specifications.	Sqm	334.80	298.92	Rupees Two Hundred Ninety Eight and Ninety Two Paise Only
6	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. Complete as per specifications.	Sqm	69.75	1600.00	Rupees One Thousand Six Hundred Only

Executive Engineer

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, Bangalore

7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specifications.	Cum	81.68	78.24	Rupees Seventy Eight and Twenty Four Paise Only

Note: The said work for sanctioned estimate cost Rs.05.00 Lakhs (Rupees Five Lakhs Only) (Incl.10%+1%KRIDL Charges + 1% Quality control tests Charges) based On "Approved SR Rates"

Signature of the ENGINEER
EXECUTIVE ENGINEER
KRIDL, BBMP, Bangalore

Executive Engineer,
Dasarahalli Division,